Integrated Watershed Management Programme (IWMP) Dhalai - V, Batch III, Dhalai Middle Upper Microwatershed

1. Reference Number: S4

2. Name of Work: Construction (Excavation) of new Pond under Watershed Development Work at Dhalai Middle Upper Micro

Watershed.

3. Name of Beneficiary: Kanu Sharma, S/O - Lt. Rajkumar Sharma.

4. Location of Work: Shashi Paul Para, Paschim Lalchari G.P., Ambassa.

5. Financial Year : 2013 - 14 (3rd year).

6. Total Cost: 54082.53

7. Name of Implementing Officer: Er. Paichafru Mog, WDT, IWMP Dhalai - V, Batch-III project.

8. Name of Supervising Officer: Dr. Alak Chowdhury, SMS (Animal science), KVK, Dhalai & Core-WDT, DMU WC.

9. Name of Estimator: Er. Paichafru Mog, WDT, IWMP Dhalai - V, Batch-III project.

10. Duration of Work: 1 (one) month approximate.

11. Date of Estimate: 4/12/2014 12:00:00 AM

Input Dimensions for Plot Specification:

Dimensions	(Metre)	Plot Area				
Length	Width	Square Metre Ganda(s) Kani(s)				
70	45	3150	39.38	1.97		

Dimensions and Calculations for Farm Pond/Community Tank

Input Dimensions for Pit/Pond (Metre):									
To	Top of Pit/Pond Bottom of Pit/Pond					Slope %			
Length	Breadth	Depth	Length	Breadth	Volume	Olope //			
61	36	1.5	58	33	3079.12	45			


Input Dimensions for Bund (Metre):								
Berm		Bund			Slope %			
Deilli	Height	Top Width	C/S Area	Length	Surface Area	Volume	Slope //	
.5	.75	2.5	2.44	214	988.68	522.16	45	

Input Dimensions for Side Drains (Metre):							
То	p of Side Dr	ain	Bottom of Side Drain	Side	Drain (in te	otal)	Slope %
Length	Breadth	Depth	Breadth	Length	C/S Area	Volume	Slope //
2.	2	1	0	2.	1	2	45

Input Dimensions for Turfing (Metre):						
Length Total width of Patch Surface Area						
214	4.62	988.68				

Input Dimensions for Clearing Jungles (Metre):							
Length Width Jungle Cutting Area							
70 45 3150							

Total volume of earth excavation work (Metre):									
Volume of Pond	Volume of Pond Volume of Side Drain Total 70 % Mechanical 30 % Mannual								
3079.12	3079.12 2 3081.12 2156.78 924.34								



Item	Desc	Unit	Rate	Quantity	Amount
1	Earth work in excavation over areas exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plain including disposal of excavated earth, lead up to 50 m and lift up to 1.5 m, disposed earth to be levelled and neatly dressed, All kind of soil hard soil.	cum	1.50	100.00	150.00
2	Earth work in excavation over areas exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plain including disposal of excavated earth, lead up to 50 m and lift up to 1.5 m, disposed earth to be levelled and neatly dressed, All kind of hard soil.	cum	73.32	100.00	7332.00
3	Earth work in excavation in foundation trenches or drains (not exceeding 1.5 mtr in width or 10 sqm on plain) including dressing of sides and ramming of bottoms lift up to 1.5 mtr including getting out the excavated soil and disposal of surplus soil as directed, with in a lead 50 mtrs. for hard soil. All kind of hard soil.	cum	73.32	100.00	7332.00
4	Turfing including dressing earth ramming pegging and watering collection and placement as per direction of the engineer incharge up to a lead of 50 mtrs.	sqm	13.00	100.00	1300.00
5	Earth work in excavation in foundation trenches or drains (not exceeding 2.5 mtr in width or 10 sqm on plain) including dressing of sides and ramming of bottoms lift up to 1.5 mtr including getting out the excavated soil and disposal of surplus soil as directed, with in a lead 50 mtrs. for hard soil. All kind of soft soil.	cum	72.00	100.00	7200.00
6	Earth work in excavation in foundation trenches or drains (not exceeding 2.5 mtr in width or 10 sqm on plain) including dressing of sides and ramming of bottoms lift up to 1.5 mtr including getting out the excavated soil and disposal of surplus soil as directed, with in a lead 50 mtrs. for hard soil. All kind soil.	cum	78.60	100.00	7860.00
7	Earth work in excavation over areas exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plain including disposal of excavated earth, lead up to 50 m and lift up to 1.5 m, disposed earth to be levelled and neatly dressed, All kind of red soil.	cum	73.32	100.00	7332.00
8	Earth work in excavation over areas exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plain including disposal of excavated earth, lead up to 50 m and lift up to 1.5 m, disposed earth to be levelled and neatly dressed, All kind of RED soil.	cum	73.32	100.00	7332.00

width as we lead up to 5	Earth work in excavation over areas exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plain including disposal of excavated earth, lead up to 50 m and lift up to 1.5 m, disposed earth to be levelled and neatly dressed, All kind of soft soil.			100.00		5213.00
Prepared By:	Approved By:		Esti	imate cost =	Rs.	51051.00
			Disp	olay board =	Rs.	1500.00
		Co	ontingency @	3.00 % =	Rs.	1531.53
			Total est	■ imate cost =	Rs.	54082.53